

No. RCB/04-02/08 /NIQ/15/2012-13

Date: - 04.2.2013

NOTICE INVITING QUOTATIONS

Work:- Providing, laying of Cast Iron Pipe in wash room and associated civil work at Regional Centre for Biotechnology, 180, Udyog Vihar Phase-I, Gurgaon (Haryana) -122 016.

Sealed quotations are invited for the work as per “Schedule of Work” attached so as to reach the undersigned on or before **22.2.2013 by 3.00 PM**. The quotations will be opened on the same day at 3.30 PM.

EMD in the shape of Demand draft of Rs. 1000/- from any Nationalised Bank drawn on State Bank of India payable at Gurgaon in favour of the Executive Director, Regional Centre for Biotechnology may also be enclosed.

TERMS AND CONDITIONS:-

1. The work shall be done as per schedule of work, specification terms and conditions and instruction of Engineer-in-charge.
2. Dimensions are indicative and the bidder is to **inspect the site** for exact dimension as required at site. Measurement will be as per actual dimensions.
3. The contractor shall have three year experience of similar work.
4. No advance payment shall be made.
5. Income Tax shall be deducted from the bill as per GOI rules for which the contractor should have a PAN No. in the name of registered company or proprietor for depositing TDS.
6. The rates shall be inclusive of all taxes, duties and cartage
7. No T&P shall be supplied by the Centre.
8. The work and items shall stand guaranteed for a period of one year from the date of its final completion.
9. Time allowed for completion of job shall be 30 days from date of issue of work order.

(Biju Mathew)
Senior Manager (A&F)

Schedule of Work

Work: Providing, laying of Cast Iron Pipe in wash room and associated civil work at Regional Centre for Biotechnology, 180, Udyog Vihar Phase-I, Gurgaon (Haryana) -122 016.

Sl. No.	Item	Qty	Rate (Rs.)	Amount (Rs.)
1	Dismantling of existing marble stones, tiles removal of Melba / Debris from site. Removal of existing CI Pipes with bends and tees and re-laying. Re- filling after required repair etc. as per site requirement and as approved by engineer-in-charge.	400 sq. ft.		
2	Providing and fixing of CI pipe with tees bends lead filler joint.	20 Ft		
3	Providing and laying of Marble stone as per existing colour and quality with 1:6 (Cement: Coarse dust) as per site requirement cutting, 08 Nos polishing.	250 Sq Ft		
4.	Plastering of wall with fine sand and providing and fixing of tiles as per existing quality and shade with 1:4 (Cement :Fine dust)	150 Sq ft		
5.	Providing and applying of two coats of white putty of reputed brand (Birla/shri Ram white cement based putty and applying double coat of enamel plastic paint as per existing shade, site requirement and as approved by engineer in charge.	350 Sq		
6	Removal of GI pipe and refixing after repairing	02 Bathroom		
7	Plastering of wall with 1:4 ratio of cement and fine sand. Curing with water for at least three days.	80 Sq fit		

Total Rs

Signature and seal of tenderer